

# Volume Report

**Project: K:\Jobs\32150007 KMO Rehab\ACAD-  
Design\\_Civil\_Design\32150007\_M4.dwg**

Alignment: R4-Salmon Street  
Sample Line Group: R4 - XSEC  
Start Sta: 400+00.000  
End Sta: 404+50.000

<u>Station</u>	<u>Cut Area</u> (Sq.ft.)	<u>Cut Volume</u> (Cu.yd.)	<u>Reusable Volume</u> (Cu.yd.)	<u>Fill Area</u> (Sq.ft.)	<u>Fill Volume</u> (Cu.yd.)	<u>Cum. Cut Vol.</u> (Cu.yd.)	<u>Cum. Reusable Vol.</u> (Cu.yd.)	<u>Cum. Fill Vol.</u> (Cu.yd.)	<u>Cum. Net Vol.</u> (Cu.yd.)
400+00.000	27.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
400+50.000	22.25	46.30	46.30	1.22	1.13	46.30	46.30	1.13	45.17
401+00.000	20.20	39.31	39.31	2.82	3.74	85.61	85.61	4.87	80.73
401+50.000	20.00	37.23	37.23	2.81	5.22	122.83	122.83	10.09	112.74
402+50.000	13.42	61.89	61.89	10.16	24.03	184.72	184.72	34.12	150.60
403+00.000	6.68	18.61	18.61	18.64	26.67	203.33	203.33	60.79	142.55
403+50.000	4.16	10.04	10.04	21.86	37.50	213.37	213.37	98.29	115.09
404+00.000	9.08	12.26	12.26	14.64	33.80	225.63	225.63	132.08	93.55
404+50.000	24.88	31.44	31.44	2.61	15.98	257.07	257.07	148.06	109.01