

Volume Report

**Project: K:\Jobs\32150007 KMO Rehab\ACAD-
Design_Civil_Design\32150007_M6.dwg**

Alignment: R6-C Street

Sample Line Group: R6-XSEC

Start Sta: 600+50.000

End Sta: 602+32.640

<u>Station</u>	<u>Cut Area</u> (Sq.ft.)	<u>Cut Volume</u> (Cu.yd.)	<u>Reusable Volume</u> (Cu.yd.)	<u>Fill Area</u> (Sq.ft.)	<u>Fill Volume</u> (Cu.yd.)	<u>Cum. Cut Vol.</u> (Cu.yd.)	<u>Cum. Reusable Vol.</u> (Cu.yd.)	<u>Cum. Fill Vol.</u> (Cu.yd.)	<u>Cum. Net Vol.</u> (Cu.yd.)
600+50.000	46.35	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
601+00.000	37.63	77.76	77.76	1.04	0.96	77.76	77.76	0.96	76.80
601+50.000	31.72	64.21	64.21	4.70	5.31	141.97	141.97	6.28	135.70
602+00.000	15.94	44.13	44.13	10.70	14.25	186.10	186.10	20.53	165.57
602+32.640	29.33	27.37	27.37	1.09	7.12	213.47	213.47	27.65	185.81